

Sales - Quote





Ms. Fran Taylor
 Boston Borough Council
 Sports and Play Office
 Princess Royal Arena
 Great Fen Road, Lincolnshire
 PE21 7PB

Quote No. SQ279571-2
 Sell-to Contact No. 41433
 Quote Date 09-03-2023
 Expiration Date 08-04-2023




Salesperson Simon Burke
 E-Mail simbur@kompan.com
 Phone No. 07972 154011

Your Reference 4x sites

Project Name EN128532 Multi-Site Works

No.	Description	Quantity	Unit of Measure	Unit Price	Amount
Central Park Play Area					
Equipment					
MSC643300-3717P	KOMPAN HCA Little Mermaid & Ugly Duckling Unit c/w Net Link, Castle, Tree & Roof, Inground	1	Pieces	28,290.00	28,290.00
					
INSTALLATION	Installation	1	Pieces	2,024.00	2,024.00
M17501-01P	KOMPAN Water Lilies 4 way Springer Inground 40cm	1	Pieces	1,020.00	1,020.00
					
INSTALLATION	Installation	1	Pieces	172.00	172.00
PCM106-0401	KOMPAN Large Horse Springer Inground 40cm	1	Pieces	1,100.00	1,100.00
					
INSTALLATION	Installation	1	Pieces	379.00	379.00
Street Furniture					
EN-SM 1800 GLENDSIDE	1800 Glenside Picnic Table Incl. K3T Bolts Powder Coated Black or Green	2	Pieces	1,236.43	2,472.86
					
	poistioned in area near toddler play - springers etc installed with grassmat wear pads				
INSTALLATION	Installation	2	Pieces	172.00	344.00

No.	Description	Quantity	Unit of Measure	Unit Price	Amount
EN-SM 1800 GLEN DA	1800 Glenside DA Picnic Table Incl. K3T Bolts Powder Coated Black or Green	2	Pieces	1,289.86	2,579.72
INSTALLATION	Installation	2	Pieces	172.00	344.00
EN-IBENCH	Install Benches - Customer to Supply Benches Benches to be Installed with grassmat wear pads	3	Pieces	157.14	471.42
Fencing					
EN-FENCE FT1 2H	Supply 1.2m High Playspec Flat Top Fencing Galvanised To create chicane styel barriers at both entrances	24	Metre	66.03	1,584.72
INSTALLATION	Installation - EN-FENCE FT1 2H G Supply 1.2m High Playspec Flat Top Fencing	24	Pieces	21.16	507.84
Removals / Groundworks					
EN-INSTALLATION	Dig out & remove from site existing toddler & infant equipment Excluding the existing Donkey springer, Giraffe climber & double car	1	Pieces	929.00	929.00
EN-INSTALLATION	Dig out & remove 5no benches from site including concrete flags	1	Pieces	770.00	770.00
EN-INSTALLATION	Relocation of existing equipment Allowance to carefully dig out & re-install the existing role play items - giraffe, double car & donkey springer Re-located into grass - Equipment jet washed and cleaned	1	Pieces	715.00	715.00
EN-INSTALLATION	Wet Pour Removal Uplift & remove from site the existing wet pour safety surfacing - including 6m2 of RBM surfacing Approx 135m2	1	Pieces	7,269.00	7,269.00
EN-INSTALLATION	Groundworks - Sub-Base Removal Allowance to dig out & remove from site the existing sub-base material including edgings - approx 125m2	1	Pieces	2,885.00	2,885.00
EN-INSTALLATION	Allowance to make good the existing tarmac surface following installation of new chicane entrance	1	Pieces	770.00	770.00
Reinstatement					
EN-INSTALLATION	Reinstatement Works - Top Soil & Turf Allowance to import top soil & turf In preparation for new grassmat surfacing Approx 135m2	1	Pieces	2,597.00	2,597.00

No.	Description	Quantity	Unit of Measure	Unit Price	Amount
Surfacing					
EN-SINGLEGRASSMAT 50	Supply & Install EcoSmart Single Layer Grass Mat All existing grass to be fully established & well maintained to give a critical fall height. New safety surfacing for - MSC643301 - Springers (including Donkey) - Giraffe & Car - Benches - Picnic Benches	108	Squ. Metre	35.71	3,856.68
Woodville Road Play Area					
Equipment					
<u>PCM113221-CUSTOM</u>	Bespoke Man-O-War with Steel & HDPE sides slide 20210125	1	Pieces	43,850.00	43,850.00
					
INSTALLATION	Installation	1	Pieces	7,246.58	7,246.58
Surfacing					
EN-SINGLEGRASSMAT 50	Supply & Install EcoSmart Single Layer Grass Mat All existing grass to be fully established & well maintained to give a critical fall height.	93	Squ. Metre	35.71	3,321.03
St Johns Play Area					
Equipment					
<u>KPL52012-CUSTOM</u>	Bespoke Large Ship, Split to create a ship bow and and stern 20210130	1	Pieces	11,870.00	11,870.00
					
INSTALLATION	Installation	1	Pieces	1,818.00	1,818.00
<u>COR201001-1001</u>	KOMPAN Spida Red, Inground 100cm	1	Pieces	6,910.00	6,910.00
					
INSTALLATION	Installation	1	Pieces	1,235.00	1,235.00
Removals					
EN-INSTALLATION	Equipment - Carefully dig out & re-install Allowance to carefully dig out & re-install the existing roundabout & 2no play panels	1	Pieces	998.00	998.00

No.	Description	Quantity	Unit of Measure	Unit Price	Amount
EN-INSTALLATION	Removals - Existing Wet Pour & Sub-Bases Reinstatement Uplift & dig out existing wet pour including sub-base from site Approx 34m2	1	Pieces	1,831.00	1,831.00
EN-INSTALLATION	Reinstatement Works - Top Soil & Turf Surfacing Allowance to reinstate area - top soil & turf Approx 34m2 required	1	Pieces	654.00	654.00
EN-SINGLEGRASSMAT 50	Supply & Install EcoSmart Single Layer Grass Mat All existing grass to be fully established & well maintained to give a critical fall height.	65	Squ. Metre	35.71	2,321.15
Garfits Lane Play Area					
Equipment					
EN-CALOO LTD	Diabolo Table Tennis Table	2	Pieces	2,142.86	4,285.72
EN-INSTALLATION	Installation Groundworks	2	Pieces	770.00	1,540.00
EN-INSTALLATION	Groundworks - Table Tennis & edging for Surfacing Surfacing To create sub-base for table tennis tables x 2 48m2 & 28 l/mtrs works include - excavation - removal of spoil from site - import & compact MOT type 1 stone - supply & install PCC edging	48	Pieces	35.71	1,714.08
EN-TARMAC 50-99	New Tarmac 70mm 50mm Base Course (20mm)	46	Squ. Metre	72.75	3,346.50
Site Preliminaries for all four sites					
EN-SITE SECURITY	Includes Heras Fencing, Skips, Site Welfare, Plant Machinery & Off Loading Equipment Heras Fencing includes - mobilisation of erecting/dismantling at each site	1	Pieces	4,397.00	4,397.00
Other					
FREIGHT	Freight	1	Pieces	9,175.75	9,175.75
VOUCHER	KOMPAN Spares Vouchers for £2,500	1	Pieces	FOC	FOC
Subtotal					167,595.05
Project Discount Amount					-25,185.50
Total GBP Excl. VAT					142,409.55
VAT Amount					28,481.91
Total GBP Incl. VAT					170,891.46

Payment Terms Net 30 days

The colour and surface texture of products and surfacing manufactured with the recycled content are influenced by the differences within the used recycled, raw materials. Therefore, minor differences in the visuality and texture not only occur, but are to be expected.

Customer responsible for offloading; however KOMPAN can provide a quotation for a Hiab delivery upon request.

KOMPAN Standard Invoicing & Payment Terms *effective from 10/10/2022.

Please see below the standard invoicing and payment terms offered by KOMPAN. If your project has specific invoicing or payment criteria, please discuss this with us at the time you place your order.

Public Sector Customers:

Full value of the project will be invoiced upon project completion, payable within 30 days from invoice date.

Private Sector Customers:

For all new customers, a request for credit terms can be made when placing your order.

If successful, the Customer will be invoiced 50% of the KOMPAN equipment value for standard and variant products at the point of order & requires pre-payment prior to release into production.

The remaining 50% of equipment value and 100% of freight is invoiced upon dispatch from the factory payable within 30 days from invoice date. Bespoke products created by KOMPAN Design Studio are invoiced 100% at the point of order and require pre-payment prior to release into production.

The remaining order value will be invoiced upon project completion, payable within 30 days.

If credit terms cannot be offered, then the Customer will be invoiced for 100% of the KOMPAN equipment value at the point of order, having 5 days to make payment to secure order being placed with the factory.

The remaining order value will be invoiced upon project completion, payable within 30 days from invoice date.

House Builders/Developers:

Invoiced for 100% of the KOMPAN equipment value at the point of order, having 30 days to make payment to secure order being placed with the factory.

The remaining order value will be invoiced upon project completion, payable within 30 days from invoice date.

Please note order value is only valid for 30 days.

Product Catalogues



Main Catalogue